

Flammability Material Test Certificate

Bunsen Burner Test Data Sheet

Test Laboratory
HAM TQ23-C

EASA.21J.019

Material Description

Security floor covering

Composition

Plastic layer coated with graining

Test Number

8050/2006

Manufacturer

Heinemann Aircraft Interiors GmbH & Co.KG

Customer/Specification

AS-yellow

Application

auf Alu-Blech

Customer Part Number

HAI-400R-yellow

Batch Number

all batches

Article Number

400R-yellow

Weight

Test Method CS/JAR/FAR 25.853

Test Requirement (Max Avg) Conditioning 24 h

Ignition Time	Material Definitions	Flame Extinguishing	Burn Length	Drip Extinguishing	Burn Rate	Flame Penetration	After Glow
For Details refer to applicable Part of App. F							
<input type="checkbox"/> 1. 60 sec Ignition Vertical Test	Interior Panels; Galleys; Under Seat Stowages	15 sec	6 inches (152 mm)	3 sec			
<input checked="" type="checkbox"/> 2. 12 sec Ignition Vertical Test	Floor Coverings; Textils; Decorative Parts; Galley Furnishings; Cushions; Electrical Conduits; Insulations; Ducts; Cargo Liners	15 sec	8 inches (203 mm)	5 sec			
<input type="checkbox"/> 3. 15 sec Ignition Horizontal Test 2,5 inch/min	Clear Windows; Signs; lighted Instruments				2,5 inch/min		
<input type="checkbox"/> 4. 15 sec Ignition Horizontal Test 4 inch/min	Small Parts; Knobs; Clips; Electrical Parts, etc.				4 inch/min		
<input type="checkbox"/> 5. 30 sec Ignition - 45 Degree	Cargo Liners; B + E	15 sec				none	10 sec
<input type="checkbox"/> 6. Blanket Test	Passenger Blanket	15 sec		3 sec			

Test Results

Sketch / Construction

Sample Number	Flame Extinguishing	Burn Length	Drip Extinguishing	Burn Rate	Flame Penetration	After Glow	Test Direction
1.	0 sec	5 mm	no drip	inch/min		sec	Lay or We't/Fill
2.	0 sec	5 mm	no drip	inch/min		sec	Lay or We't/Fill
3.	0 sec	5 mm	no drip	inch/min		sec	Lay or We't/Fill
Average	0 sec	5 mm	no drip	inch/min		sec	Lay or We't/Fill
1.	sec	mm		inch/min		sec	Warp
2.	sec	mm		inch/min		sec	Warp
3.	sec	mm		inch/min		sec	Warp
Average	sec	mm		inch/min		sec	Warp

Test Date : 04.12.2006


Tested by : Damwilk

Engineering/Work Order

Pass

Fail

Approved :



Comments :